

3D X-ray CT of fatigue damage in fibre composites

Jespersen, Kristine Munk; Zangenberg Hansen, Jens ; Lowe, Tristan; Withers, Philip J.; Mikkelsen, Lars Pilgaard

Publication date: 2016

Document Version Peer reviewed version

Link back to DTU Orbit

Citation (APA):

Jespersen, K. M., Zangenberg Hansen, J., Lowe, T., Withers, P. J., & Mikkelsen, L. P. (2016). 3D X-ray CT of fatigue damage in fibre composites. Poster session presented at 24th International Congress of Theoretical and Applied Mechanics, Montreal, Canada.

General rights

Copyright and moral rights for the publications made accessible in the public portal are retained by the authors and/or other copyright owners and it is a condition of accessing publications that users recognise and abide by the legal requirements associated with these rights.

• Users may download and print one copy of any publication from the public portal for the purpose of private study or research.

- · You may not further distribute the material or use it for any profit-making activity or commercial gain
- You may freely distribute the URL identifying the publication in the public portal

If you believe that this document breaches copyright please contact us providing details, and we will remove access to the work immediately and investigate your claim.



DTU Wind Energy Department of Wind Energy



3D X-ray CT of fatigue damage in fibre Blade cross-section Unidirectional (UD) composites

Kristine M. Jespersen^{1*}, Jens Zangenberg², Tristan Lowe³, Philip J. Withers³, and Lars P. Mikkelsen¹ ¹Department of Wind Energy, Technical University of Denmark, Roskilde, Denmark (*kmun@dtu.dk) ²LM Wind Power Blades, Composites Mechanics, Kolding, Denmark ³Manchester X-Ray Imaging Facility, School of Materials, University of Manchester, Manchester, United Kingdom

A uni-directional (UD) glass fibre composite made from a non-crimp fabric (NCF) was investigated by 3D X-ray computed tomography (CT) to study the fatigue damage at different stages of the fatigue life. The

damage was found to appear as local UD fibre fracture regions close to the so-called supporting backing layer, which seemed to have an important role in the location of the damage initiation. Furthermore, the damage appeared as 3D regions containing both clusters and chains of fibre fractures, and it was concluded that considering this problem in 3D seemed to be important in order to obtain realistic results.

UD glass fibre composite material is used for the load carrying parts of the wind turbine

UD NCF GF composite

Δσ

blade considered (marked with green). The glass fibres are gathered in bundles which are held in place by stitching them to a backing layer. The glass fibres are in the range of 17-21 microns in diameter and are surrounded by a polyester resin.



The above figure shows the main loads on wind turbine blades. The rotation of the blade causes the gravitational load on the blade to change direction twice (two load cycles) during a single rotation. Furthermore, the wind variation causes repeated loading with high variation.

Fatigue damage in wind turbine blade materials

With a lifespan of around 20 years, a wind turbine blade experiences repeated loading in the order of 10⁸ cycles, which is much higher than for most other structures. Therefore fatigue is one of the main limiting factors when designing long blades. However, the main load carrying parts of the blades are made from UD NCF composite and their fatigue damage mechanism is complex and not well understood. To improve the materials and decrease safety factors, it is important to gain understanding on the fatigue progression behaviour.





The above figure shows an example of a blade cross-section and an indication of the predominant loading types acting on the main beams made from UD glass fibre composite (green).

The above figure shows the typical stiffness degradation behaviour and damage progression postulate for considered UD composite based on 2D SEM observation [2]. Off-axis cracks are said to initiate in the supporting backing bundles causing an initial stiffness drop. UD fibre fractures then cause the stiffness to gradually decrease with increasing cycles until final failure.

Experimental method

Fatigue tests (R=0.1) were carried out on four 410mm long butterfly shaped specimens and stopped at different number of cycles. X-ray CT experiments were performed on a Zeiss X-radia Versa 520. As the image resolution in Xray CT scans is decreasing for increasingly large cross-sections, cut-outs are considered to obtain high resolution (1.2 µm voxel resolution). This results in a small field of view (2.4mm), however high resolution is necessary to see individual UD fibre fractures.



Observed damage in 3D

The UD fibre fractures were individually marked and shown in 3D. The main observations are as follows:

- UD fibre fracture regions are only seen where backing bundles intersect and at the same time is in contact with the UD bundle



Acknowledgements

- This research was conducted using mechanical testing equipment from DTU Center for Advanced Structural and Material Testing (CASMAT), Grant No. VKR023193 from Villum Fonden.
- We would like to acknowledge the assistance provided by the Manchester X-ray Imaging Facility, which was funded in part by the EPSRC (grants EP/F007906/1, EP/F001452/1 and EP/I02249X/1)
- Financial support from CINEMA: "the allianCe for ImagiNg of Energy MAterials", DSF-grant no. 1305-00032B under "The Danish Council for Strategic Research" is gratefully acknowledged.
- We would like to thank LM Wind Power for manufacturing of test specimens.

References

- 1. K. M. Jespersen et al., 2016. Fatigue damage assessment of uni-directional glass/polyester composite using x-ray computed tomography (submitted)
- 2. J.Z Hansen, 2013. The effects of fibre architecture on the fatigue life-time of composite materials, PhD thesis, Technical University of Denmark.
- 3. R.P.L. Nijssen, 2006. Fatigue life prediction and strength degradation of wind turbine rotor blade composites, PhD thesis, Delft University of Technology.

DTU Wind Energy

Risø Campus - Frederiksborgvej 399 - DK-4000 Roskilde - Denmark

Composites and Materials Mechanics

www.vindenergi.dtu.dk